

Frequently Asked Questions for Cabling Project RFP

1. Is there a time frame to complete each location? **Completion depends on the number of cables run and access to the branches. Cable maintenance should be completed within a week or 7 business days. All really depends on the project.**
2. Are there rough in done by an electrician? **Any additional network drops are usually near existing power outlets. If and when additional power is needed, PGCMLS will hire and electrician to add the additional power needed. The cabling vendor is responsible for adding the network drops only.**
3. Are Plenum rated cable required? **Yes**
4. Will a low voltage permits be required if so what is the specifications? **Low voltage permits are required for new construction projects, but not for maintenance.**
5. Any brand name of hardware cable required? **No**
6. How soon after the survey will work start? **For all cabling needs, a survey is recommended. Work should start within 7 to 10 days after survey is completed. Coordinating start time with PGCMLS is necessary to determine access and the best time to start.**
7. Will one or more site be available to be work on at the same time? **Yes**
8. Will the staff be able to have access to the location before the opening time and will the staff be able to stay late if needed the libraries? **Access will be available before opening time when patrons are not in the branches. Late hours work will depend on staff availability to open and close buildings.**
9. Are any of the Library facilities included in the scope of this contract covered by any type of special designation such as "Historical Building", etc? **No.**
10. In the preparation of the drop pricing, what is the average length of the Cat 6e cable drops to be included in the sliding scale? Is plenum cable to be used in the pricing exercise? **List plenum cabled as outline below. Pricing should include installed, terminated, tested and labeled including wall plate, jack and certification report.**

CAT 6e Plenum Cable:

0-150 feet – Pulls, include pricing for:

(0-10)

(11-50)

(51-100)

(101-200)

151 – 300 feet – Pulls, include pricing for: (0-10)

(11-50)

(51-100)

(101-200)

11. Is the per drop pricing to include the cost of the cable, jacks, miscellaneous materials and labor? **Pricing should include installed, terminated, tested and labeled including wall plate, jack and certification report.**
12. The payment terms outline on page seven of the RFP state “The Library prefers to make a lump sum payment once the project has been completed”. This statement seems to imply a single payment at the end of the contract. Is that the County’s intention? If not, please clarify the payment terms to reflect how the Contractor will be paid relative to each task undertaken within this contract. **Single payment for services will occur after completion of work; additional services will be invoiced separately.**
13. Are J-Hooks acceptable (spaced in accordance with NEC requirements) in lieu of horizontal raceway above suspended ceilings where no existing raceway is in place? **Yes**
14. Since some sites may not need them and the site conditions are undetermined at this time, for the purposes of this RFP, are the costs for raceway and or/ j-hooks to be listed and/or billed separately? **J-Hooks and raceway pricing should be listed and billed for each project.**
15. Does PG County Memorial Library System require metal or plastic raceway? **Plastic**
16. Can we assume each location will need to be walked and quoted as they are presented for the work to determine specific circumstances? **Yes, each location will need to be walked and survey in order to provide an accurate quote.**
17. Is there a more detailed scope available or should we simply create one based on our assumptions? **Please use the existing scope and added information provided to questions submitted concerning the RFP.**
18. Are there any special products requirements? **No**
19. Is there going to Voice vs. Data? **We have both voice and data.** Also if there is voice will it be terminated on the patch panels or on a wall mounted termination block? **Patch panel.**
20. The specs say if ten drops or more provide patch cord. Just to clarify if there are less than ten drops NO patch cords need to be provided? **Patch cords are needed for all drops.**

-----End-----